

Rogue Valley Sewer Services (RVSS)

Sanitary Sewer General Notes

1. The sanitary sewer system is to be owned and maintained by RVSS.
2. Inspection and acceptance is the responsibility of RVSS.
3. All work shall conform to the latest version of the American Public Works Association (APWA)/Oregon Department of Transportation (ODOT) Standard Specifications for Public Works Construction and RVSS Standard Specifications and Drawings. RVSS Standards shall take precedence.
4. A preconstruction meeting between the contractor and RVSS is required prior to starting work.
5. Contractor shall notify RVSS 48 hours in advance of construction.
6. Contractor shall obtain prequalified status with RVSS prior to performing work on sewer to be owned and maintained by RVSS, including taps on existing sewer mains.
7. Confined space certification will be verified prior to performing work on RVSS facilities requiring confined space entry. Personal Protective Equipment including but not limited to gas detection meters, fall protection and a confined space rescue system will be required.
8. Contractor is responsible for the testing of sanitary sewer facilities per RVSS Specifications. Testing of sewer facilities is subject to RVSS acceptance.
9. Contractor is responsible for the management of existing sewer flows during construction. Upon request, a sewer bypass plan must be submitted to RVSS for approval prior to bypassing or blocking existing sewer.